

SAMPLE SCOPE OF SERVICES

TASK ORDER NO. T____

Contract No. 1443C200009____

US Reservation 72 Rehabilitation

National Mall and Memorial Parks

SCOPE:

In accordance with the terms and conditions of the Indefinite Delivery / Indefinite Quantity (IDIQ) contract, the contractor shall perform the work of this Request for Proposal (RFP) for the National Park Service (NPS) as described below.

The work of this task order shall be performed in accordance with the DSC Workflow Website <http://www.nps.gov/dsc/workflows/>.

In case of conflict between this task order and the DSC Workflow Website, this task order shall take precedence over and shall be used in lieu of such conflicting portions.

In case of conflict between this task order and the Base IDIQ contract, this task order shall take precedence over and shall be used in lieu of such conflicting portion.

CONFIDENTIALITY: The information developed under this task order is the property of the U.S. Government and shall be kept in strict confidence.

PERFORMANCE PERIOD: The work of this task order shall be provided from ____ through ____.

PROJECT IDENTIFICATION:

PMIS Number:

Project Title: US Reservation 72 Rehabilitation

Project Location: National Mall and Memorial Parks, District of Columbia

POINTS OF CONTACT:

Contractual:

Contracting Officer (CO):

Contract Specialist (CS):

Technical:

Project Manager (PM):

Contracting Officer's Technical Representative:

Park POC:

STANDARD SERVICES:

Comply with standard services per the IDIQ contract, Section C, except as modified elsewhere in this task order.

I. PROJECT DESCRIPTION:

This project will rehabilitate U.S. Reservation 72, which is under the jurisdiction of the National Park Service, National Mall and Memorial Parks in Washington, D.C. This project will preserve the character of the L'Enfant era reservation (circa 1791) and will maintain, or replace in kind, character defining features installed in 1904 and 1930s. (See attached historic details and specifications.) The rehabilitation at Reservation 72 has been designed with local community members and will enhance the overall public recreational use of the reservations.

MATERIALS PROVIDED BY THE NATIONAL PARK SERVICE

Attachments:

Photo Attachment

Renovation Plans (Selected Pages)

Quarter-round curb detail

Drawing 822_80007 detail of walks (1 page)

Grey sidewalk mix spec (which should be used for concrete walkways; a finer grain aggregate is needed to match existing)

II. SCOPE OF SERVICE REQUIREMENTS

Reservation 72 ("Chinatown Park") is located on the south side of Massachusetts Avenue, at 6th, 5th and I Streets, N.W. This park is a "sister" park with Reservation 74 on the north side of Massachusetts Avenue. Typically, the landscape treatment and site furnishings installed in "sister" reservations bisected by a diagonal roadway would be mirror images. They were designed as a whole park, situated as two triangular units, bisected by a roadway. The rehabilitation project for Reservation 72 (and later, Reservation 74) will:

- Remove the damaged asphalt and concrete paving and replace in kind throughout.
- Preserve the majority of existing quarter-round curb. Replace inappropriate quarter-round curb with new quarter-round curb according to NPS specifications and add corresponding end posts. Add new quarter round curb along restored turf areas and realigned walkways.
- Rehabilitate the existing fence, relocate some sections to the exterior edges of the reservation, and add new sections of fence to match existing as noted below.
- Rehabilitate existing NPS park benches and add an additional three benches to Res. 72.
- Replace the existing "tulip" style trash receptacles with Victor Stanley receptacles.
- Re-grade and reseed dirt social paths worn in the grass panels of the reservations and restore turf as needed throughout. Some new turf areas will be established as noted below.
- Maintain or add steel edging along all turf areas.
- Repair or replace existing quick-couplers and activate the water system within reservations.

In addition, rehabilitate the following in **Reservation 72**:

- See drawing, "Renovation Plans of U.S. Reservation 72, NPS, Sponsor: Downtown DC Business Improvement District," 11/16/07, updated 12/08/2007.
- Expand the pedestrian entrances by shortening the existing fence lines and turf areas.
- Removing the north/south section of fence on the 5th St. side and reinstall it to extend the existing fence on the south side. Relocate this fence to the exterior of the turf area.
- Remove one section of fence on the west side to install a turf area. Maintain north/south alignment and add additional fence to round the corners of the turf area.
- Retain the existing quarter-round curb on the north and south sides of the park and add new quarter-round curb and end posts on the east and west sides.
- Maintain existing trees and plant new flowering trees on the south exterior turf area.

III. FEE AND PAYMENT


Comply with fee and payment requirements per the IDIQ Contract, Section G, and as stated herein.

The Contractor shall be paid for travel and lodging in accordance with IDIQ contract, Section G. Travel costs and all other direct costs shall be included in the firm fixed price for the work.


After completion of the work and as a prerequisite to the final payment on this task order, the Contractor shall furnish to the Contracting Officer a **Release of Claims arising out of this Task Order**. Such claims as are asserted by the Contractor and excepted from operation of the Release shall be listed in spaces provided after the word "except" and shall be referenced to correspondence or other identifying data, together with monetary amount for each major claim item.

The Government obligation for performance of this task order beyond this phase is contingent upon the Government's needs and availability of funds from which payment for contract purposes can be made. No legal liability on the part of the Government for any payment may arise for performance under this contract beyond the amount that has been authorized through the issuance of written task orders.



The sum as in this task order is obligated as the firm-fixed price for the furnishing of all supplies and services required to accomplish all services required under this task order.




ELEVATION
DETAIL OF TRANSITION BETWEEN CONCRETE COPING & METAL EDGING




PLAN
SCALE - THREE INCHES EQUAL ONE FOOT




PLAN OF EXPANSION JOINT
SCALE 3/4" = 1'-0"



SECTION THRU WALK
SCALE - 3" = 1'-0"



SECTION THRU EXPANSION JOINT
SCALE - 3" = 1'-0"



PLAN
TYPICAL PORTION OF BITUMINOUS CONCRETE WALKS

DR. BY: W.S.	U.S. DEPARTMENT OF THE INTERIOR	DATE: 7/26/95
TR. BY: W.S.	NATIONAL PARK SERVICE	SHEET NO. 2 OF 5 SHEETS
CK. BY: W.S.	FOLGER PARK	DWG. NO. N.C.P.1651
Revised:	DETAIL OF WALKS	
	SCALE - 3/4" = 1'-0"	
	DRAWN BY: EASTERN DIV., DR. OF PLANS & DESIGN	

17-7

FILE No. 405 10/13 '04 15:51 ID:QC

FAX: 4107219843

PAGE 6

October 13, 2004

Kalos Constr
P.O. Box 60874
Washington, DC 20039



Re: Lincoln Memorial - Washington DC Job #: 0401

Gentlemen:

We respectfully submit the following concrete mix design for your approval and use on the above referenced project. We certify that our mix designs will meet project specification in 28 days when handled, placed, tested and cured following ASTM and ACI "Standards and Recommended Practices".

In order to ensure optimum performance, Aggregate Industries, Inc. reserves the right to make adjustments to our mix designs at any time. All will deliver all materials in accordance with C94.

CEMENT: Type I / II ASTM C150
FINE AGGREGATE: ASTM C33
COARSE AGGREGATE: # 8 ASTM C33
AEA: ASTM C260
WRDA: ASTM C494
SLUMP: 4 +/- 1 Inch

4000 / AF / Exposed Pca
40651912

CEMENT	(LBS/CU/YD)	611
SAND	(LBS/CU/YD)	1165
STONE	(LBS/CU/YD)	1950
AEA	(OZS/CU/YD)	4.0
WRDA	(OZS/CU/YD)	18.0
WATER	(LBS/CU/YD)	275

*Please note that the weights in this mix were adjusted for exposing.

**Please note that color is not an integral part of the mix. However, the desired color may be obtained through dispatch as an extra product and added at the plant when needed.

Please take note. Product numbers identify all of our mixes. Please advise all personnel of the approved product numbers for this project and direct them to request the appropriate number when placing the order with dispatch.

Respectfully Submitted,
Aggregate Industries, Inc.

Sharon Carr
Asst Manager Technical Services

AGGREGATE INDUSTRIES MID ATLANTIC
c/o Gary Seiden, Sales Representative

6401 Golden Triangle Drive
Suite 400
Greenbelt, Maryland 20770

Tel: 801 - 982 - 1400
Fax: 301 - 513 - 0012

An AGGREGATE INDUSTRIES PLC Company
www.aggregate-us.com

Submital Type: ☒ Shop Drawing
☐ Sample

Review is only for limited purposes set forth in the Contract Documents.

APPROVED: (For Incorporation in the Work)
☒ Approved as Submitted
☐ Approved as Noted

DISAPPROVED: (Resubmit Required)
☐ Make Corrections
☐ As Noted, Develop Replacement

INCOMPLETE: (Resubmit Required)
☐ Complete and Resubmit
☐ Submit Missing Portions

Sharon Carr 10/25/04
CHIEF MILL

William V. Walsh Construction Company, Inc.
Contractor Certification.

☒ Approved

☐ Approved as Noted

I hereby certify this submittal has been reviewed for accuracy, completeness and general compliance with the contract requirements.

Reviewed By: *[Signature]*

Date: 10-19-04

Approval of this submittal is subject to the provisions of the contract drawings and specifications. This action is for general concurrence only and requires the approval of McKissack & McKissack of Washington, Inc.

B. Concrete Coloring:

1. Reinforced Exposed Aggregate Concrete: QC Color Tech E-Graphite, 6.5 sack mix, one bag per cubic yard of concrete, to match existing inner circle sidewalk.
2. Contractor shall provide manufacturer with approved concrete mix design for color calibration prior to constructing samples or placing any concrete.

2.5 CONCRETE MIXTURES

A. Prepare design mixtures, proportioned according to ACI 301, with the following properties:

1. Compressive Strength (28 Days): 3000 psi.
2. Maximum Water-Cementitious Materials Ratio at Point of Placement: 0.50.
3. Slump Limit: 4 inches, plus or minus 1 inch.
4. Air Content: 6 percent plus or minus 1.5 percent.

2.6 CONCRETE MIXING

- A. Ready-Mixed Concrete: Measure, batch, and mix concrete materials and concrete according to ASTM C94. Furnish batch certificates for each batch discharged and used in the Work.

PART 3 EXECUTION

3.1 EXAMINATION

- A. Proof-roll prepared subbase surface below concrete pavements, and/or aggregate base with heavy pneumatic-tired equipment to identify soft pockets and areas of excess yielding.

3.2 EDGE FORMS AND SCREED CONSTRUCTION

- A. Set, brace, and secure edge forms, bulkheads, and intermediate screed guides for pavement to required lines, grades, and elevations. Install forms to allow continuous progress of work and so forms can remain in place at least 24 hours after concrete placement.
- B. Clean forms after each use and coat with form-release agent to ensure separation from concrete without damage.

3.3 STEEL REINFORCEMENT

- A. General: Comply with CRSI's "Manual of Standard Practice" for fabricating, placing, and supporting reinforcement.

3.4 JOINTS

- A. General: Form construction, isolation, and contraction joints and tool edgings true to line with faces perpendicular to surface plane of concrete. Construct transverse joints at right angles to centerline, unless otherwise indicated.
- B. Construction Joints: Set construction joints at side and end terminations of pavement and at locations where pavement operations are stopped for more than one-half hour unless pavement terminates at isolation or expansion joints.

Reservation 72 (Massachusetts Ave, 5th-6th, and I Streets, NW)

Res. 72- Social trail (noted as “earthen trail” on drawing) to be re-graded and re-seeded in center grass panel (view looking north).



Res. 72- Section of fence on east edge of reservation (left of photo) to be removed and replaced along new pathway alignment. Center pathway to be straightened and nose of both grass panels to be reduced and edged with new quarter-round curb and end posts (see historic quarter-round curb detail). Brick DC sidewalks to remain. Reservation pathways to be replaced with new concrete/asphalt walkways with 6 in. concrete expansion joints to replicate existing pathway. (See historic walkway detail and concrete mix specifications.)



Photo Attachment: U.S. Reservation 72 Rehabilitation

Res. 72- Fence along west edge (left of photo) to be maintained with one section removed on north side (in view) to expand the pedestrian area on corner of the reservation. Grass area in front of fence will be expanded and edged with quarter-round curb and end posts at entrances. Benches will be rehabilitated and reinstalled. Pavement will be replaced with concrete/asphalt walkways to match existing (see above). "Tulip" style trash receptacle will be replaced with Victor Stanley style receptacle. Tree (right) to be maintained.



Close-up of existing concrete/asphalt walkway with 6 in. expansion joints. Walkways to be replaced in kind.



Photo Attachment: U.S. Reservation 72 Rehabilitation

Res. 72- Detail of quarter-round curb and end posts to be replicated at entrances.
(See historic detail.)




RENOVATION PLANS OF U. S. RESERVATION 72

NATIONAL PARK SERVICE

SPONSOR:


DOWNTOWN DC BUSINESS IMPROVEMENT DISTRICT



KEY MAP

SHEET LIST:

1. TITLE SHEET
2. EXISTING CONDITIONS
3. DEMOLITION PLAN
4. HARDSCAPE PLAN AND DETAILS
5. GRADING PLAN
6. EROSION & SEDIMENT CONTROL PLAN
7. EROSION & SEDIMENT CONTROL DETAILS
8. CONSTRUCTION ACCESS PLAN



LOCATION MAP
NOT TO SCALE

PROJECT TITLE

RESERVATION 72
RENOVATION PLAN
NATIONAL PARK SERVICE

SPONSORS

CHINESE CONSOLIDATED
BENEVOLENT ASSOCIATION

DOWNTOWN DC BUSINESS
IMPROVEMENT DISTRICT

NATIONAL PARK SERVICE

PROJECT NUMBER

04018

DRAWING TITLE

TITLE SHEET

SCALE:

DATE :

DRAWN BY :

CHECKED BY :

DRAWING NUMBER

SHEET

1

OF

8

11/16/07

PROJECT TITLE
**RESERVATION 72
RENOVATION PLAN
NATIONAL PARK SERVICE**

SPONSORS

**CHINESE CONSOLIDATED
BENEVOLENT ASSOCIATION
DOWNTOWN DC BUSINESS
IMPROVEMENT DISTRICT
NATIONAL PARK SERVICE**


PROJECT NUMBER 04018

DRAWING TITLE

EXISTING CONDITIONS

SCALE: AS SHOWN
DATE: 11/18/2007
DRAWN BY:
CHECKED BY:
DRAWING NUMBER

SHEET 2 OF 8



PROJECT TITLE
**RESERVATION 72
RENOVATION PLAN
NATIONAL PARK SERVICE**

SPONSORS
**CHINESE CONSOLIDATED
BENEVOLENT ASSOCIATION**
**DOWNTOWN DC BUSINESS
IMPROVEMENT DISTRICT**
NATIONAL PARK SERVICE

PROJECT NUMBER 0019

DRAWING TITLE
DEMOLITION PLAN


SCALE: AS SHOWN
DATE: 12/06/07
DRAWN BY: HYY
CHECKED BY: PHL
DRAWING NUMBER

L - 100

SHEET OF

GENERAL NOTES:

1. CONTRACTOR SHALL CALL MISS UTILITY TO LOCATE AND MARK ALL UTILITY LINES PRIOR TO THE BEGINNING OF ANY WORK.
2. CONTRACTOR SHALL BE RESPONSIBLE FOR THE PROTECTION OF ALL EXISTING UTILITY LINES DURING THE DEMOLITION AND CONSTRUCTION PERIOD. LIMIT OF WORK IS THE ENTIRE ISLAND BLOCK.
3. CONTRACTOR SHALL BE RESPONSIBLE FOR THE PROTECTION OF ALL EXISTING ELEMENTS UNLESS OTHERWISE NOTED TO REMAIN IN THE SURROUNDING SIDEWALK AREAS DURING THE ENTIRE CONSTRUCTION PERIOD. REPAIR AND RESTORE ANY DAMAGE WHEN TIED IN WITH NEW WORK.
4. ALL EXISTING BENCHES SHALL BE SAVED AND REHABILITATED AS PER NATIONAL PARK SERVICE SPECIFICATIONS FOR REUSE IN THE PARK.
5. THE PANELS OF REMOVED EXISTING IRON FENCE SHALL BE SALVAGED AND REHABILITATED AS PER NATIONAL PARK SERVICE SPECIFICATIONS FOR REUSE IN THE PARK.
6. NEW PRECAST CONCRETE PLANTER CURBS SHALL MATCH THE EXISTING CURBS IN COLOR AND TEXTURE. CONTRACTOR SHALL MAKE A SAMPLE PIECE AT SITE FOR REVIEW AND APPROVAL PRIOR TO ANY INSTALLATION.
7. WHEN EXTENDING PAVEMENT INTO THE PARK THE CONTRACTOR SHALL MAINTAIN THE SURFACE OF NEW PAVEMENT FLUSH WITH THE EXISTING SIDEWALK. MAINTAIN THE PLANTER CURBS AT 8" HIGH CONSISTENTLY AND FINE GRADE THE LAWN AREAS ADJACENT TO THE CURBS AS INDICATED ON THE PLAN.
8. CONTRACTOR SHALL MAINTAIN THE WORK AREA CLEAN AND ORDERLY. REMOVE ALL DEBRIS FROM SITE IMMEDIATELY AFTER EACH DAY.
9. CONTRACTOR SHALL GIVE THE NATIONAL PARK SERVICE 5 DAYS ADVANCE NOTICE TO CONDUCT A SITE INSPECTION WHEN ALL WORKS ARE COMPLETED. THE NATIONAL PARK SERVICE WILL ISSUE A PUNCHLIST FOR ANY PROBLEM TO BE CORRECTED.
10. AFTER ALL ITEMS OF THE PUNCHLIST ARE CORRECTED, THE NATIONAL PARK SERVICE WILL CONDUCT A FINAL SITE INSPECTION AND ISSUE AN INITIAL ACCEPTANCE UPON SATISFACTION.
11. CONTRACTOR SHALL WARRANT ALL MATERIALS AND WORK FOR A PERIOD OF ONE YEAR FROM THE DATE OF INITIAL ACCEPTANCE. CONTRACTOR SHALL REPAIR OR REPLACE ANY DEFECT OR FAILURE WITHOUT CHARGE DURING THE ONE YEAR WARRANTY PERIOD. NATIONAL PARK SERVICE WILL ISSUE A FINAL ACCEPTANCE AT THE END OF THE ONE YEAR WARRANTY PERIOD UPON SATISFACTION.



1 DEMOLITION PLAN
1/8" = 1'-0"

ANNUAL REPORT

UPON THE

IMPROVEMENT AND CARE OF PUBLIC BUILDINGS AND GROUNDS, AND
CARE AND MAINTENANCE OF THE WASHINGTON MONU-
MENT. IN THE DISTRICT OF COLUMBIA,

IN THE CHARGE OF

THOMAS W. SYMONS,

MAJOR, CORPS OF ENGINEERS, COLONEL, U. S. A.,

AND

CHAS. S. BROMWELL,

CAPTAIN, CORPS OF ENGINEERS, COLONEL, U. S. A.:

BEING

APPENDIX D D D

OF THE

ANNUAL REPORT OF THE CHIEF OF ENGINEERS FOR 1904.



WASHINGTON:
GOVERNMENT PRINTING OFFICE.
1904.

In connection with the subject of the United States public reservations in the city of Washington, it is considered proper to invite attention to the desirability of correcting a typographical error which appears in one portion of the act of Congress approved July 1, 1898 (vol. 30, Statutes, p. 570).

The act referred to reads:

* * * * *

SEC. 2. That the park system of the District of Columbia is hereby placed under the exclusive charge and control of the Chief of Engineers of the United States Army, under such regulations as may be prescribed by the President of the United States, through the Secretary of War.

The said park system shall be held to comprise:

(a) All public spaces laid down as reservations on the map of eighteen hundred and ninety-four accompanying the annual report for eighteen hundred and ninety-four of the officer in charge of public buildings and grounds.

(b) All portions of the space in the streets and avenues of the said District, after the same shall have been set aside by the Commissioners of the District of Columbia for park purposes.

Provided, That no areas less than two hundred and fifty square feet between sidewalk lines shall be included within the said public system and no improvements shall be made in unimproved park spaces in streets between building lines or building lines prolonged until the outlines of such portions as are to be improved as parks shall have been laid out by the Commissioners of the District of Columbia: *And provided further*, That the Chief of Engineers is authorized temporarily to turn over the care of any of the parking spaces included in Class B above to private owners of adjoining lands under such regulations as he may prescribe and with the condition that the said private owners shall pay special assessments for improvements contiguous to such parking under the same regulations as are or may be prescribed for private lands.

The error referred to occurs in the sentence which reads:

And provided further, That the Chief of Engineers is authorized temporarily to turn over the care of any of the parking spaces included in Class B above to private owners, etc.

and consists in the fact that Class B should read Class A, because it is the reservations mentioned in Class A whose care is intended to be turned over temporarily to private owners of adjoining lands, and not those in Class B. It is therefore recommended that Congress be requested at its next session to correct the error in question by suitable legislation.

PARK CURBING.

Substantial and gratifying progress has been made during the year in constructing cement copings, with corner posts of similar materials, at the entrances to park walks, around reservations, in place of the iron post and chain fences formerly inclosing them. A total length of 10,809 linear feet of coping and 137 corner posts were built during the year, the work being done under contract. The parks thus inclosed are enumerated in the following table:

Table showing the extent of artificial stone coping constructed as borders around United States public reservations during the fiscal year ending June 30, 1904.

Park.	Length.	Number of corner posts.
Dupont Circle:	<i>Fect.</i>	
Around the statue	190.0	
Around the circle	1,067.0	32
Iowa Circle	1,063.0	36
Scott Circle	314.7	
Thomas Circle	572.2	
Farragut Square	1,495.0	14
Reservation No. 57, Massachusetts avenue, Twenty-second and Q streets NW	292.2	
Reservation No. 62, Massachusetts avenue and N street, between Sixteenth and Seventeenth streets NW	440.0	8
Reservation No. 64, Massachusetts avenue and N street, between Fifteenth and Sixteenth streets NW	469.0	6
Reservation No. 68, Massachusetts avenue and L street, between Eleventh and Twelfth streets NW	589.0	8
Reservation No. 69, Massachusetts avenue and I street, between Tenth and Eleventh streets NW	402.0	8
Reservation No. 140, New Hampshire avenue, Twenty-first and M streets NW	390.6	
Reservation No. 143, New Hampshire avenue, Twentieth and O streets NW	156.3	
Reservation No. 141, New Hampshire avenue, Seventeenth and S streets NW	474.0	8
Reservation No. 145, New Hampshire avenue, Seventeenth and T streets NW	321.0	
Reservation No. 149, Connecticut avenue, Twentieth and Q streets NW	452.0	
Reservation No. 150, Connecticut avenue, Eighteenth and M streets NW	396.0	
Reservation No. 150a, Connecticut avenue, Eighteenth and N streets NW	189.0	
Reservation No. 163, Vermont avenue, Thirteenth and O streets NW	345.3	
Reservation No. 188, Indiana avenue, Third and D streets NW	380.0	6
Reservation No. 37, Pennsylvania avenue, Third and B streets SE	345.0	
Reservation No. 209, Maryland avenue, First and A streets NE	436.0	8
Reservation No. 207, Maryland avenue, Seventh and D streets NE	228.0	3
Total	10,809.3	137

A tracing showing the design of the coping is herewith.

The laying of this coping necessitated the following work being done:

In Iowa Circle, Scott Circle, Thomas Circle, and reservations Nos. 37, 62, 63, 66, 143, 153, 188, and 207, the ground back of the coping was raised and the surface resodded. In the case of all the other parks and park places mentioned in the table the sod and soil were removed from the surface of the ground, the grades raised 8 inches with clay filling, the soil replaced and a double row of sod laid around the borders inside the coping.

PARK WATCHMEN.

I especially desire to invite attention to the force of park watchmen, which force is improperly named, inadequate in point of numbers, and insufficiently paid. The designation of watchmen does not describe the members of this force and their duties. They are strictly policemen, with all the powers of the regular police force, and their duty is to maintain proper police control over the parks. This requires a great deal of delicacy on the one hand in dealing with women and children, and on the other the roughest and most dangerous kind of police work in dealing with toughs and offenders of all kinds. The duty of the men is not simply to watch the parks, but is also to protect the respectable people, especially women and children, in their full enjoyment, and unmolested by bad men and dissolute women. It would be a satisfaction to the men of the force and aid them in the performance of their duties to be designated as policemen, for offenders are sometimes averse to being cautioned by watchmen, and question the authority of a watchman to make an arrest, as it is generally supposed that no one but

SRS, U. S. ARMY.

used as borders around United
during June 30, 1904.


	Length.	Number of corner posts.
Acres.		
100.0		
1,057.0		32
1,063.0		30
314.7		
602.2		
1,096.0		14
292.2		
Acres NW		
Length and	440.0	8
Length and	469.0	6
Length and	589.0	8
Length and	602.0	8
Acres NW	590.8	
Acres NW	150.2	
Acres NW	474.0	8
Acres NW	821.0	
Acres NW	452.0	
Acres NW	398.0	
Acres NW	189.0	
Acres NW	246.3	
Acres NW	380.0	8
Acres NW	346.0	
Acres NW	438.0	8
Acres NW	228.0	8
10,809.8		137

is herewith.

following work being

and reservations Nos.
and back of the coping
se of all the other parks
and soil were removed
used 8 inches with clay
of sod laid around the

once of park watchmen,
a point of numbers, and
men does not describe
they are strictly police-
force, and their duty is
4. This requires a great
h women and children,
ons kind of police work
s. The duty of the men
protect the respectable
air full enjoyment, and
It would be a satisfac-
e performance of their
rs are sometimes avers
he authority of a watch
posed that no one but



CORPS OF ENGINEERS.
U.S. ARMY.
Office of Public Buildings and Grounds.
WASHINGTON, D. C.

FULL SIZE
PARK COPING
CONCRETE

Approved
Frederick S. Brown
May 1910.

LENGTHS 7' x 8' - 6" Radius

Note:

An eight inch coping has been put around the following Parks during the fiscal year ending June 30, 1909.

Name.	Length in feet.
Dupont Circle	1,067.
Iowa "	1,063.
Scott "	314.7
Thomas "	572.2
Farragut Square	1,095.
Rossy. 57. Mass. Ave. 22 nd - Q St. NW.	292.2
" 62 " " N. Oct. 16 - 17 "	440.
" 64 " " " 15-16 "	469.
" 68 " " I. " 11-12 "	589.
" 69 " " L. " 10-11 "	602.
" 140 N.E. 21 - 22 "	300.
" 143 " " 20 - 21 "	156.3
" 144 " " 17 - 18 "	474.
" 145 " " 17 - 18 "	321.
" 149 Conn. 20 - 21 "	452.
" 150 " " 18 - 19 "	396.
" 150 " " 18 - 19 "	189.
" 100 Ver. " 13 - 14 "	346.
" 188 Ind. " 3 rd - 4 th "	389.
" 37 Penn. " 3 rd - 4 th "	S.E. 348.
" 203 Md. " 1 - 2 "	N.E. 736.
" 207 " " 7 - 8 "	223.

